
Ukraine Demo

**MHP “Ukraine”, DBFZ & EE
“Germany”**

Thessaloniki, 19.06.24



Co-funded by
the European Union

innovations in the
BIOMETHA^{ne}
uni**VERSE**

In-situ biological methanation (IBM)



Objectives

Demonstration of an innovative in-situ biological methanation pathway using a gas recirculation system, as well as the construction and implementation of a similar system and technology at a biogas plant in Ladyzhyn, Ukraine

New implementation of the container-type DEMO installation will allow conducting research and testing on existing biogas installations in Ukraine and Europe



Biological Methanation (IBM) in Ukraine: Locations for technology testing

■ Main location



**MHP: LADYZHIN,
VYNNITSIA REGION**

Feedstock: 300 t/d of
chicken manure and
agricultural residues

**Capacity: 12 MW
Biogas 44 000 000 m³**



■ Additional locations in Ukraine

**MHP: DNIPRO,
DNIPRO REGION**

Feedstock:
120t/d chicken manure
and agricultural residues

**Capacity: 5,5 MW
Biogas 22 000 000 m³**



■ Potential locations in Ukraine / Europe

UKRAINE / EUROPE

Feedstock:
agricultural residues

Capacity: 1 - 26 MW



A.1. Demonstration of IBM in 50 L lab-scale reactors

Task 1.1. Preparing the laboratory setup



Task 1.2. Establishing a stable anaerobic digestion (AD) process



Task 1.3. Establishing a stable IBM process



Task 1.4. Determining process parameters



A.1. Demonstration of IBM in 50 L lab-scale reactors

➤ Laboratory setup



- 1: AD reactor
- 2: Mass flow controller
- 3: H₂ tank
- 4: Gas meter
- 5: Gas pump
- 6: Stirrer
- 7: Monitor
- 8: Water trap



© Daniel N. Dzofou
(DBFZ)

© Ivan Traksler (MHP)



A.1. Demonstration of IBM in 50 L lab-scale reactors

➤ Operating parameters

Operating Parameters	Unit	MHP	DBFZ
Working volume of reactors	g	40,000	40,000
Temperature	°C	39 ± 3	40 ± 2
Hydraulic Retention Time	days	60 – 80	50 – 70
Organic loading rate	(g _{VS} /L day ⁻¹)	3 ± 0.2	4 ± 0.2
daily feed (g FM)		390 – 550	672 – 770
Cow manure		X	✓
Chicken manure		✓	✓
Corn silage		✓	✓
Water		✓	X

	Unit	Effluent		Cow manure		Chicken manure		Corn silage	
		MHP	DBFZ	MHP	DBFZ	MHP	DBFZ	MHP	DBFZ
pH		8.50 ± 0.10	7.78 ± 0.13	-	7.23 ± 0.34	-	-	-	-
FOS/TAC	g _{FOS} /g _{CaCO3}	0.16 ± 0.03	0.19 ± 0.06	-	0.86 ± 0.35	-	2.33 ± 1.07	-	-
NH ₄ -N	g.L ⁻¹	4.10 ± 0.63	3.40 ± 0.60	-	1.91 ± 0.21	6.68 ± 1.19	5.85 ± 5.16	-	-
TS	%	5.79 ± 0.4	8.63 ± 1.54	-	9.47 ± 0.95	48.9 ± 0.68	32.86 ± 1.48	31.15 ± 7.20	30.07 ± 3.76
VS	% _{TS}	81.0 ± 8.15	73.93 ± 7.75	-	75.79 ± 1.35	78.20 ± 2.25	70.18 ± 5.20	95.19 ± 1.28	96.48 ± 0.74



A.1. Demonstration of IBM in 50 L lab-scale reactors

➤ Establishing a stable IBM process

- H₂ addition & determination of optimal process

DBFZ				
Volume		Ratio	40 °C	42 °C
H ₂ flow rate	3.5 mL.min ⁻¹	~ 4.6 %	2W	
	7 mL.min ⁻¹	~ 9.3 %	4W	
	10.5 mL.min ⁻¹	~ 14 %	3W	3W

MHP				
Volume		Ratio	39 °C	42 °C
H ₂ flow rate	0.6 mL.min ⁻¹	~ 1.4 %	1W	
	0.6 mL.min ⁻¹	~ 1.6 %	3W	1W
	1.0 mL.min ⁻¹	~ 2.6 %		2W

- Bioaugmentation



Aim: Increase the hydrogenotrophic methanogen community in DBFZ reactors by daily addition of $\sim 7.5 \text{ mL.L}_{\text{reactor}}^{-1}.\text{d}^{-1}$ of *Methanobacterium formicicum* for at least 1 month



A.1. Demonstration of IBM in 50 L lab-scale reactors

➤ Establishing a stable IBM process


- Screening of the microbial consortia (before H₂ addition)



A.1. Demonstration of IBM in 50 L lab-scale reactors



Result to date: Specific biogas production, H₂, CO₂ and CH₄ content in biogas

DBFZ reactors



A.2. Construction of an IBM demo reactor 10 m³

■ MHP Demo – Tasks

- Task 2.1 Definition of the Technical Task 
- Task 2.2 Concept design 
- Task 2.3 Detailed technical Design 
- Task 2.4 Design of Controls and Instruments 
- Task 2.5 Equipment List 
- HAZOP 
- Task 2.6 Installation of the Demo Plant 
- Task 2.7 Commissioning of the Demo Plant 




A.2. Construction of an IBM demo reactor 10 m³

■ Main Structure of the Plant

- Standard sea container as a basis structure
- The system should be able to be transported using standard container trailers.
- The container is divided into the following separate sectors:
 - SCADA and control room
 - Electrolysis room
 - machine room
 - Digester

Containerized In situ Demo Plant Ukraine




A.2. Construction of an IBM demo reactor 10 m³

▪ Technical Detailed Design

Containerized In situ Demo Plant Ukraine

The pilot plant must have the essential characteristics of a conventional biogas plant in its equipment and structure, as well as mirroring the processes in the laboratory plants. The following priorities therefore took centre stage in the design:

- Mesophilic process with temperatures between 37 - 45°C
- Gas circulation system in the fermenter, which corresponds to that of a large scale plant
- Integration of hydrogen distribution and injection into the gas circulation system.



Deviations

- Purchased and installed 2 containers for demo installation
- Container 1 - fermenter 10m3 and container 2 - electrolyzer
- Equipment for production of hydrogen in container 2 was purchased
- Installation of equipment in container 2 has begun
- Equipment for container 1 (biogas production) was purchased
- Work on the development of a fermenter 10m3 has begun
- Delivery of the main equipment - end of June 2024



#Biomethaverse

Thank you!

Follow Biomethaverse:

www.biomethaverse.eu 

[@European_Biogas](https://twitter.com/European_Biogas) 

[@European Biogas Association](https://www.linkedin.com/company/european-biogas-association/) 

Contact: DBFZ, MHP & EE

Email:

Daniel.Dzofou.Ngoumelah@dbfz.de

a.dombrovskiy@mhp.com.ua

reik@ellmann-gmbh.de

Co-funded by the European Union. Views and opinions expressed are however those of the author(s) only and do not necessarily reflect those of the European Union or CINEA. Neither the European Union nor the granting authority can be held responsible for them.



Co-funded by
the European Union